As a part of your end year networking project, you are required to design and implement Vic Modern Hotel network. The hotel has three floors; in the first floor there three departments (Reception, store and Logistics), in the second floor there are three departments (Finance, HR and Sales/Marketing), while the third floor hosts the IT and Admin. Therefore, the following are part of the considerations during the design and implementation.

- 1. There should be three routers connecting each floor (all placed in the server room in IT department).
- 2. All routers should be connected to each other using serial DCE cable.
- 3. The network between the routers should be 10.10.10.0/30,10.10.10.4/30.10.10.10.8/30
- 4. Each floor is expected to have one switch (placed in the respective floor).
- 5. Each floodis expected to have WIFI networks connected to laptops and phones.
- 6. Each department is expected to have a printer.
- 7. Each department is expected to be in different VLAN with the following details

1st Floor;

- Reception- VLAN 80, Network of 192.168.8.0/24
- •Store- VLAN 70, Network of 192.168.7.0/24
- Logistics- VLAN 60, Network of 192.168.6.0/24

2nd Floor;

- Finance- VLAN 50, Network of 192.168.5.0/24
- •HR-VLAN 40, Network of 192.168.4.0/24
- •Sales- VLAN 30, Network of 192.168.3.0/24

3rd Floor;

- Admin- VLAN 20, Network of 192.168.2.0/24
- IT-VLAN 10, Network of 192.168.1.0/24
- 8. Use OSPF as the routing protocol to advertise routes.
- 9. All devices in the network are expected to obtain IP address dynamically with their respective router configured as the DHCP server.
- 10. All the devices in the network are expected to communicate with each other.
- 11. Configure SSH in all the routers for remote login.
- 12. In IT department, add PC called Test-PC to port fa0/1 and use it to test remote login. 13. Configure port security to IT-dept switch to allow only Test-PC to access port fa0/1 (use sticky method to obtain mac-address with violation mode of shutdown.)